

REMONUMENTATION COMMISSION
APR 06 1995

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 1 47

corners in
 CASS (County)

Located In: CASS COUNTY REMONUMENTATION
 Corner Code ##

Public Land Survey	T 6 S R 16 W	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Ann L. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 370

Register of Deeds Stamp & File Number

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman Dale C. Kessler
 Date Dec 22, 1993

Lot No. _____, Recorded Plat _____
 Private Claims _____

December 9-93

Bert W. Prestine, in a field survey on February 17, 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 present manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 certified below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

D-13 South quarter corner Section 32, T. 6 S., R. 16 W.
 Govt.
 Set post, Wm. Brookfield 1827
 White Oak N 89 3/4° E 10.86 chains
 No other trees near

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 1/2" or 3" steel post in marsh in 16" of water.
 Indiana & Michigan Electric Co. shows corner unmarked, post only. Believed to be
 steel post & show distance of 2635.0' from Southwest corner of Section 32,
 measure 2634.18'

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" plastic pipe over 2 1/2" pipe & filled with concrete. Set Cass County
 remonumentation cap in top & marked corner.
 Once R.R. Tie fence corner post West 36.90'
 Once 11" Double Maple S 5° W 17.15'
 Once 12" Burr Oak N 40° W 40.35'
 Once 24" Burr Oak N 60° W 39.65'
 Once going North is East 1.1'



by Robert W. Prestine Date December 27, 1994

Surveyor's Michigan License No. 18662