

**REMONUMENTATION**  
**APR 06 1995**  
**COMMISSION**

STATE OF MICHIGAN  
 CASS COUNTY  
 RECEIVED FOR RECORD

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

CASS COUNTY REMONUMENTATION

1994 DEC 28 PM 1 47

CASS (County)	Located In:	Corner Code #
Public Land Survey	T <u>6 S</u> R <u>16 W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Ann L. Simmons*  
 CLERK/REGISTER

LIBER **2** PAGE **372**

Register of Deeds Stamp & File Number

Validated by Peer Group  
 In Accordance With P.A. 345  
 Chairman *Dale C. Kelly*  
 Date *Dec 22, 1993*

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

*December 16-93*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert W. Prestine in a field survey on December 20, 1994,  
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 present manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

E-13 Southwest corner Section 33, T. 6 S., R. 16 W.  
 Govt.  
 Set post, Wm. Brookfield 1827  
 White Oak 26" N 82 3/4° E 91 links  
 White Oak 24" N 23° W 88 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone 4" in diameter x 10" long with hole in top over flat stone 10" in diameter  
 x 5" thick with cross, remains of post under stone.  
 Believed to be stone shown on Indiana & Michigan Electric Co. survey April 30, 1931.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed stones and set Cass County remonumentation monument.  
 Nail & witness tag in South side 17" Wild Cherry N 86° 30' W 33.48'  
 Nail & witness tag in North side 12" Burr Oak S 75° W 7.87'  
 Nail & witness tag in East side 14" Burr Oak N 9° 30' W 26.92'  
 Nail & witness tag in Southwest side 6" Hackberry N32° W 23.22'  
 102.78 feet West of Northwest corner Section 4, T. 7 S., R. 16 W. (Monument)



Recorded by *Robert W. Prestine*

Date December 27, 1994

Surveyor's Michigan License No. 18662