

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Cass  
(County)

Located In: \_\_\_\_\_ Corner Code // \_\_\_\_\_

1. Public Land Survey		T 7S	R 13W	M-3
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section	S 12	T 7S	R 13W	7, 14
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Donald L. Bissell, in a field survey on October, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

M-3	7.	14.
NE Cor. Sec. 12	E 1/8 Cor. of NE 1/4, Sec. 12	E 1/8 Cor. of SE 1/4, Sec. 12
Found 1/2" rod	Found 1" Pipe @ Road intersection	Set 4" x 36" Conc. Mon. w/alum cap at midpoint between E 1/4 Cor. and SE Cor., Sec. 12 and in old fence corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3	7.	14.
NE Cor. Sec. 12 - 1/2" rod	E 1/8 Cor. of NE 1/4, Sec. 12	E 1/8 Cor. of SE 1/4, Sec. 12
S30°E - 46.54' - Cor. Power Pole	1" Pipe	4" x 36" Conc. mon.
S67°W - 41.78' - 16" W. Oak	N28°E - 43.18' - 8" Cherry	N49°E - 31.72' - 6" HICKORY
N47°W - 45.60' - 14" R. Oak	N42°W - 58.07' - 9" Sassafrass	S70°E - 13.72' - 7" Hickory
N20°W - 76.99' - 5" Maple	S63°W - 63.96' - 6" F. Pine	S38°W - 16.62' - 16" Cherry
South - 82.50' - 1/2" rod in Mon. box		at North edge Pine plantation
NW Cor. Sec. 7, T7S, R12W		
Spike & Tag in Trees and P.P.		

Signed by Donald L. Bissell

Date \_\_\_\_\_

Surveyor's Michigan License No. 18655



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1983