

Ratified by Peer Group
 In Accordance With P.A. 348
 Chairman Dale L. Kesler
 Date December 20, 1995

Liber 00003 Page 0034

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 CASS COUNTY REMONUMENTATION

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded

For corners in

CASS
 (County)

Located In:

Corner Code #

12-28-1995 16:07:34

1. Public Land Survey	T	<u>7</u>	R	<u>13</u>	<u>M-2</u>
NORTH PORTER TWP.	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

Ann L. Simmons
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, DALE L. KESLER, in a field survey on NOVEMBER 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Dec. 26, 1826 - William Brookfield - Set post - Set by going north on east line Section 1 from Southeast corner Section 1 - 40.00 Chains - 2640' - Set post - 5' White Oak - S. 36° W. 64 Links (42.9'), 14" White Oak - N. 31 1/2° W. 22 Links (14.52')
- Apr. 4, 1877 - Amos Smith, County Surveyor - Set post - Measured from the Southeast corner Section 1 to East Quarter Corner Section 1 - 39.94 Chains (2636.04') - Witness for East Quarter corner Sec. 1, 9" Black Oak - N. 70 1/4° W. 10 Links (6.60')
- Apr. 7, 1989 - Fred Labar - Calculated position of E. 1/4 Post - No Witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no corner or its accessories. Set the East Quarter corner by single proportionate using the original 1826 measurements and our measurements between the Southeast corner and the Northeast corner of Section 1. The prorated distance from the Southeast corner to the East Quarter corner is 2638.63 feet and from the East Quarter corner to the Northeast corner is 2856.31 feet.

MAR 27 1996

MAR 27 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" X 24" Iron pipe with aluminum cap in a monument box and is accepted as a careful and faithful re-establishment of the position of the original corner.

- Nail w/washer - S. side 6" Oak tree - S. 52° 10' W. 49.0'
- Nail w/washer - W. side 20" Oak tree - S. 74° 26' E. 33.60'
- Nail w/washer - SW. side 22" Oak tree - S. 45° E. 38.80'
- Nail w/washer - E. side 4" Twin Oak tree - S. 89° 14' W. 43.65'
- Centerline gravel road - 3.0 feet West



Signed by Dale L. Kesler
 Surveyor's Michigan License No. No. 38117

Date December 28, 1995