

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman Dale L. Kesler
 Date December 20, 1995

Liber 00003 Page 0033

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CASS (County) Located In: _____ Corner Code # _____

CASS COUNTY REMONUMENTATION

1. Public Land Survey	T <u>7</u> R <u>13</u>	<u>M-7</u>
NORTH PORTER TWP.	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded

12-28-1995 16:07:20
 Ann L. Simmons
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, DALE L. KESLER, in a field survey on NOVEMBER 28, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Dec. 25, 1826 - William Brookfield - Set post - North on east line Sec. 24 from east quarter corner, Sec 24 - 40.00 chains, (2640.00')
- White Oak tree - S. 20 Deg. W. - 91 Links (60.06')
- 8" Poplar tree - N. 9 1/3 Deg. W. - 1.19 Chains (78.54')
- Oct. 1989 - Donald Bissell - Found 1/2" Rod, Recorded in Liber, 2, Page 321, Jan. 30, 1990
- 8" Triple Red Oak - S. 70 Deg. E. 33.62'
- 7" Cherry - S. 32 Deg. E. 46.67'
- East - 3' Center road
- Spike/Tag - Plus blaze in trees


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod in monument box. The accessories of a 1989 survey by Donald Bissell verify location of corner. Distances to adjacent corners were reasonable and consistent. Accepted 1/2" rod as best evidence of corner.

MAR 27 1996
 COMMISSIONER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 3/4" X 24" iron pipe with aluminum cap in place of 1/2" rod in monument box and is accepted as a careful and faithful perpetuation of the original corner.
- Nail w/witness tag in power pole - N. 75 Deg. W. 27.35'
- Nail w/witness tag in 40" Oak tree - N. 75 Deg. E. 32.70'
- Nail w/witness tag in 20" Triple Oak tree - N. 46 Deg. e. 39.65'
- Nail w/washer in 7" Cherry tree - S. 32 Deg. E. 46.70'
- Centerline of gravel road - East 3.00'



Signed by Dale L. Kesler
 Surveyor's Michigan License No. No. 38117

Date December 20, 1995