

Ratified by Peer Group
 In Accordance With P.A. 945
 Chairman Dale C. Kil
 Date October 5, 1995
 For corners in Porter Township

CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded

12-01-1995 10:09:24

Ann L. Simmons
 REGISTER OF DEEDS

Liber 00003 Page 0014
 Register of Deeds Stamp & File Number

Cass (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>13W</u>	<u>M-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Christian F. Marbach, in a field survey on November 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Monument: Post set with references, (Britain, 1828)
 Accessories: 30" Poplar S 31½° W 11 Links
 10" Beech N 35 2/3° W 38 Links
 Subsequent Restoration: 3/4" iron pipe (Wightman-Peirce, Inc., 1-26-94)
 Witnesses: N 20° W 22.30' Power pole
 - 75.5' SW corner mobile home
 - 74.0' SW corner mobile home
 N 70° E 58.10' Light pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Monument Found: 3/4" iron pipe in gravel drive, North side of asphalt road; Teesdale Lake Street.

MAR 27 1996
 COMMISSIONER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Monument: Concrete monument (36" long)/rebar with aluminum tablet, 0.4' below ground stamped "Cass County Remonumentation".
 Witnesses: N 20° E 63.72' SE corner concrete porch for mobile home.
 N 70° E 58.19' P.K. Nail with cap set 1' high in SE side of light pole.
 S 15° W 94.43' P.K. Nail with cap set in NE root at base of twin 30" Walnut.
 N 20° W 22.31' P.K. Nail with cap set 1' high in NE side of power pole.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

signed by Christian F. Marbach Date 11-27-95
 Surveyor's Michigan License No. 37280

