

Ratified by Peer Group  
 in Accordance With P.A. 345  
 Chairman Ann L. Keeler  
 Date October 5, 1995  
 For corners in Porter Township

CASS COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00003 Page 0017

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-01-1995 10:09:58

Ann L. Simmons  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Cass (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>13W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Christian F. Marbach, in a field survey on November 13, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Original Monument: Post set with references (Britain, 1828)  
 Accessories: 15" Blue Ash N 65 1/3° E 15 Links  
 14" Beech West 53 Links

Subsequent Restoration: Bruce Jones, 1963, stone found with metal under wood stake.  
 Witnesses: 12" Maple N 42° W 11.7', 7" Maple S 42° E 26.7',  
 11" Maple S 55° W 16.8'  
 Daniel Rahilly, Nov. 1982, painted stone found 1' below surface  
 (Liber 2, Pg. 268).  
 Witnesses: 25" Maple N 27° E 8.15', 9" Maple S 62° E 9.51',  
 10" Maple S 35° W 4.48', 16" Maple N 45° W 11.90'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Monuments Found: Stone with cross cut in top 0.8' below surface.

MAR 27 1996  
 COMMISSIONER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Monument: Found existing stone with cross cut in top, Set monument box on top of stone; box is 0.5' lower than surface of ground.

Witnesses: N 10° E 8.79' P.K. Nail in washer found 4' high West side of 36" Ash.  
 S 65° E 9.55' P.K. Nail in washer found 1' high in North side of 10" Maple.  
 S 20° W 4.47' P.K. Nail in washer found 1' high in East side of 12" Ash.  
 N 45° W 11.79' P.K. Nail in washer found 1' high in East side of 18" Maple.

Stone is 1' West and 1' North of intersection of woven wire fence.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Chris F. Marbach Date 11-27-95  
 Surveyor's Michigan License No. 37280