

July 5, 1994
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

RECORDATION CERTIFICATE
 Implementation of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

1994 JUL 12 AM 8 39

Ann L. Simmons
 CLERK/REGISTER

LIBER **2** PAGE **343**

Register of Deeds Stamp & File Number

Validated by Peer Group
 In Accordance With P.A. 345
 Chairman *Dale C. Fealy*
 4-14-94

For corners in
 Cass
 (County)

Corner Code #

1. Public Land Survey	T 7 S R 14 W	K-1 (NE Cor., 2)
	T _____ R _____	Calvin Twp.
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Chris F. Marbach, in a field survey on May 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-1, Original Monument: Post (Britain, 1828)
 Accessories: 15" Oak S49°W, 75lks. (49.5')
 Subsequent Observations (as per survey): 3/4" iron pipe (Michiana Surveyors, 1975)
 Stone (Prestine, 1978)
 Stone; set 1/2" rebar (Barger Eng., 1981)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1, Rebar found next to point of stone. Old fence rows to West and North
 Corner perpetuated as per the following surveys:

- Distance to SW Cor. Sec. 36, T6S, R14W
- 1.32' East of K-1 (Britain, 1828)
- 1.32' East of K-1 (Prestine, June 1978)
- 1.32' East of K-1 (Marbach & Brady, 1994)



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1, Monument: 1" iron pipe with aluminum tablet set in 4" dia. concrete monument; 3' long. Corner stone is buried under said monument.

- Witnesses:**
- P.K. & cap in W. Side 24" Oak; N0°E, 35.16'
 - P.K. & cap in W. Side 12" Oak; N65°E, 37.49'
 - (all measured with tape) P.K. & cap in E. Side 4" Beech; S65°E, 30.51'
 - P.K. & cap in E. Side 10" Oak; S30°W, 13.64'
 - P.K. & cap in SW Side 14" Sassafras; N53°W, 28.05'

Recorded by *Chris F. Marbach* Date July 5, 1994
 Surveyor's Michigan License No. 37280