

CASS COUNTY REMONUMENTATION

STATE OF MICHIGAN
CASS COUNTY
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 JUL 12 AM 8 40

For corners in

Cass (County)	Located In:	Corner Code #
1. Public Land Survey	T 7 S R 14 W	L-1 (N $\frac{1}{2}$ Cor., 1)
	T _____ R _____	Calvin Twp.
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Ann L. Simmons
CLERK/REGISTER

LIBER 2 PAGE 345

Register of Deeds Stamp & File Number

Validated by Peer Group
In Accordance With P.A. 345
Chairman Dale C. Keady
Date 7-14-94

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Chris F. Marbach, in a field survey on May 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1, Original Monument: Post (Britain, 1828)

Accessories: 5" Beech S64°W, 571ks. (37.62')

Subsequent Observations (as per survey): Stone (Prestine, 1978)
(Barger Eng., 1981)
(Wightman-Peirce, 1993)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1, Found stone at corner.
Found Oak Tree at S $\frac{1}{2}$ Cor. Sec. 36, T6S, R14W

Distance 0.66' East of L-1 (computed from 1828 survey)
Distance 0.66' East of L-1 (measured by Marbach & Brady)

Found iron pipe in box at M-1

Distance 2651.67' (measured by Wightman-Peirce, 1993)
Distance 2651.80' (measured by Marbach & Brady, 1994 ; with E.D.M.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1, Monument: 1" iron pipe with aluminum tablet set in 4" dia. concrete monument;
3' long. Corner stone is buried under said monument.

Witnesses: P.K. & cap in NW Side 12" Wild Cherry; N30°E, 15.27'
P.K. & cap in N. Side 36" Oak; N90°E, 22.60'
(all measured with tape) P.K. & cap in N. Side 36" Oak; S0°E, 1.62'
P.K. & cap in SW Side 16" Oak; N35°W, 19.09'



Signed by *Chris F. Marbach* Date July 5, 1994

Surveyor's Michigan License No. 37280