

Ratified by Peer Group

Liber 00003 Page 0050

In Accordance With P.A. 345

CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Chairman Dale L. Kule
Date December 20, 1995
For corners in

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-28-1995 16:12:02

Ann L. Simmons
REGISTER OF DEEDS

CASS (County)	Located In:	Corner Code #
1. Public Land Survey	T 7 S R 15 W	C-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Robert W. Prestine, in a field survey on December 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2 East quarter corner Section 6, T. 7 S., R. 15 W.
Govt wits gone
Wm. Brookfield D.S. Oct. 1828
White Oak 24" N 6 1/2° W 3.19 chains
Yellow Oak 15" S 1° W 5.79 chains


RECEIVED
RECORDATION
MAR 27 1996
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2
Found 1/2" over 1" pipe. (1" is 12" deep below asphalt.)
1" by J.L. Corbit R.L.S. 1956
1/2" over by R.W. Prestine R.L.S. #18662 May 1977

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 Set 3/4" x 24" iron pipe & Cass Co. remon cap in monument box.
Nail & washer in South side Elec. pole N 72° W 57.8'
Face R.R. tie fence corner post West 26.75' (Nail in face)
Nail & washer in North side 4" Box Elder S 76° E 24.95'
Nail & washer in East side 10" Elm S 30° W 54.7'
This position is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by Robert W. Prestine

Date December 28, 1995

Surveyor's Michigan License No. 18662