

Ratified by Peer Group  
 In Accordance With P.A. 315  
 Chairman Dale Keen  
 Date December 20, 1995

CASS COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00003 Page 0045

For corners in  
CASS (County) Located In: Corner Code ##

1. Public Land Survey	T <u>7</u> S R <u>16</u> W	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-28-1995 16:10:48  
 Ann L. Simmons  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert W. Prestine in a field survey on December 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 A-2  
 West Quarter corner, Section 6 T. 7 S., R. 16 W.  
 This corner not set by Govt.  
 Unable to find any record of this corner, other than corner set by myself, May 1978.

MAR 27 1996  
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 A-2  
 Found corner, 3/4" by 30" pipe, as set May 1978 12" deep in open field. Set in line with N.W. corner Section 6 & 1/8 corner to South, (both stones with cross) & 1534.15' South of N.W. corner, being S.W. corner Singer property (stone) & using East & West 1/2 line as established by others & produced West to county line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-2  
 Set 4" round Cass County Remonumentation monument 12" deep in open field.  
 Nail & washer in West side 32" White Wood N 44° 30' E 220.0'  
 Nail & washer in West side of 22" Beech N 65° E 182.4'  
 Nail & washer in West side 26" Beech S 89° E 180.1'  
 Berrien County corner is North 21.2' (1/2" iron in 2 1/2" pipe)  
 This position is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by Robert W. Prestine Date December 28, 1995  
 Surveyor's Michigan License No. 18662