

Ratified by Peer Group  
 In Accordance With P.A. 345  
 Chairman Dale L. Keel  
 Date December 20, 1995  
 For corners in

CASS COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00003 Page 0046

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-28-1995 16:11:00

Ann L. Simmons  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| CASS<br>(County)                      | Located In:                | Corner Code -# |
|---------------------------------------|----------------------------|----------------|
| 1. Public Land Survey                 | T <u>7 S</u> R <u>16 W</u> | <u>A-3</u>     |
|                                       | T _____ R _____            | _____          |
|                                       | T _____ R _____            | _____          |
|                                       | T _____ R _____            | _____          |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____    | _____          |
|                                       | S _____ T _____ R _____    | _____          |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____    | _____          |
|                                       | S _____ T _____ R _____    | _____          |
| 4. Lot No. _____, Recorded Plat _____ |                            |                |
| 5. Private Claims _____               |                            |                |

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Robert W. Prestine, in a field survey on December 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Southwest corner Section 6, T. 7 S., R. 16 W.

Govt Wits gone.  
 Wm. Brookfield D.S. June 1828.  
 Govt.  
 Beech 19" N 5° E 30 links  
 Beech 24" S 76° E 29 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3  
 Found 1/2" pipe set by D.M. Dreher R.L.S. #13580, 1962.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3  
 Set 4" round Cass County Remonumentation monument  
 Nail & washer in West side 14" Ash N 54° E 30.45'  
 Nail & washer in North side 15" Sycamore N 76° W 30.77'  
 Nail & washer in West side 20" Sycamore S 46° W 44.42'  
 Center of 30" Cotton Wood South 90.4'

Govt jog in Cass County 39 links South of Berrien County corner (25.74 feet).  
 Berrien County corner 1/2" iron.  
 This position is accepted as a careful and faithful reestablishment of the position of the original corner.



Signed by Robert W. Prestine Date December 28, 1995

Surveyor's Michigan License No. 18662