

**CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Cass (County)	Located In:	Corner Code #
1. Public Land Survey	T 7S	R 16W A-6
	T	R
	T	R
	T	R
2. Property Controlling S in Section	T	R
	T	R
3. Miscellaneous Property in Sec.	S	R
	S	R
	T	R
	T	R
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-20-1999 15:28:24

Ann L. Simmons
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, V.J. Strebs, in a field survey on 6 December, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT SET IN ORIGINAL GOVERNMENT SURVEYS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1870+/- CASS COUNTY SURVEYOR, SET POST HALFWAY AND ON LINE BETWEEN SOUTHWEST AND NORTHWEST CORNERS; 12 3/4 LINKS NORTH OF EAST 1/4 CORNER OF SECTION 13, T7S, R17W

1980 BARGER ENGINEERING, FOUND CORNER 7.9 FEET NORTH OF EAST 1/4 CORNER OF SECTION 13, T7S, R17W

1999 WIGHTMAN AND ASSOCIATES FOUND SMALL STONE AND 2" X 3" STEEL GUY WIRE STAKE 8.48 FEET NORTH OF REMONUMENTED EAST 1/4 CORNER OF SECTION 13, T7S, R17W

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE, SET 4" DIAMETER CONCRETE MONUMENT WITH ALUMINUM CAP IN TOP, 8.42 FEET NORTH OF EAST 1/4 CORNER OF SECTION 13, T7S, R17W
WIT. TAG IN 10" POPLAR S 45° E - 1.61
M.S.H.D. TAG IN R.R. TIE FENCE POST N 50°W 12.57'
FOUND IRON PIPE NORTH 23.34'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by V.J. Strebs
Surveyor's Michigan License No. 26469

Date 12-15-99



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

RF

FEB 24 2000

SECTION