

REMONUMENTATION COMMISSION
APR 06 1995

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 1 46

CASS COUNTY REMONUMENTATION

corners in	Located In:	Corner Code #
CASS (County)		
Public Land Survey	T <u>7</u> S R <u>16</u> W	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Ann L. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 369

Register of Deeds Stamp & File Number

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman, Dale C. Fisher
 Date Dec. 22, 1993

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

December 8 - 93
 Robert W. Prestine in a field survey on September 2, 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 present manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 witnessed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:


C-1 Northwest corner Section 5, T. 7 S., R. 16 W.
 Govt..
 Set post, Wm. Brookfield 1827
 White Ash 9" S 65° E 45 links
 White Oak 10" S 32° W 60 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone, Indiana & Michigan Electric Co. survey of April 30, 1931, shows stone in
 place 2.5 feet East of corner post 2.26 chains East of Southwest corner Section 32,
 T 6 S., R. 16 W. (149.16 feet)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed stone and set Cass County Remonumentation Monument with stone around
 Nail & witness tag in Northwest side 8" Box Elder S 44° W 16.48'
 Nail & witness tag in South side 10" Wild Cherry West 21.53'
 Nail & witness tag in North side R.R. Tie corner post West 2.5'
 Pokagon Township corner West 149.16 feet. (Monument)



by Robert W. Prestine

Date December 27, 1994

Surveyor's Michigan License No. 18662