

MAY 16 1997

COMMISSION

CASS COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Liber 00003 Page 0075

STATE OF MICHIGAN COUNTY OF CASS Recorded

For corners in Ontwa Township

Table with columns: Cass (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

01-31-1997 10:52:32

Ann L. Simmons REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Vertical text: Ratified by Peer Group In Accordance With P.A. 345 Chairman Dale C. Key Date 12-4-96

I, Christian F. Marbach, in a field survey on September 6, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A triangle marker is located at the intersection of row 8 and column C.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Original Monument: Set post corner to Fr1. Sections 19 & 20, 13.62 chains East of 38 Mile Post (Brookfield, 1827)

Accessories: 15" White Oak, N 42.5° E - 28 links 16" White Oak, N 31° W - 47 links

Subsequent Restoration: (1) Found boat spike over stone (Peirce 8/16/71, Liber 1, Pg. 103) Plat Monument, West 60.0'; Centerline pavement, East - 9.4'; Fence corner R/W, West - 35.9'

(Continued on reverse side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Evidence Found: (C-8) Monument found in monument box

(C-7) Monument found in monument box See: (Peirce 8/16/71, Liber 1, Pg. 103) (Jones 10/23/73, Liber 1, Pg. 337) (Peirce 11/10/78, Liber 2, Pg. 142)

Distance (C-8) to (C-7): 36.42 chains (2403.72') (Brookfield, 1827) 2421.00' (Peirce 8/16/71, Liber 1, Pg. 103) 2420.83' (Prestine 5/31/88, Liber 2, Pg. 295) 2420.76' (Marbach & Brady, 1995)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Monument: Left existing monument undisturbed. This monument is accepted as careful and faithful reestablishment of the position of the original corner.

Accessories:

R/W marker, West - 36.05' R/W marker, East - 47.70' West leg of "Welcome to Michigan" sign, N 45° E - 51.50'



Signed by [Signature]

Date 12-9-96

Surveyor's Michigan License No. 37280

A. (Continued)

- (2) Set standard monument in monument box (Peirce 11/28/78, Liber 2, Pg. 170)
Plat Monument, West 60.0'; R/W marker, West - 35.90'; R/W marker, East - 47.90'
- (3) Standard corner in monument box (Prestine 5/31/88, Liber 2, Pg. 295)
Concrete monument, West - 60.0'