

FEB 19 1998

Liber 00003 Page 0081

CASS COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF CASS Recorded

SECTION For corners in Ontwa Township

Table with columns: Cass (County), Located In: (T, S, R), Corner Code = #. Includes entries for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

02-19-1997 14:20:50

Ann L. Simmons REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Vertical stamp: Ratified by Peer Group In Accordance With P.A. 345 Chairman Date 2-11-97

I, Christian F. Marbach, in a field survey on September 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Monument: Set post corner to Fr1. Sections 22 & 23, 15.26 chains East of 41st Mile Post (Brookfield, 1827)

Accessories: 8" Hickory, N 12° E - 29 links 9" Hickory, N 68.5° W - 86 links

Subsequent Restoration: Iron pipe set (Peirce 6/2/69 - Survey for I & M Electric line easement)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Evidence Found: Nothing found

Method Applied: North line of Fr1. Sec. 22 (I-7) to (G-7) was split at midpoint to set (H-7) (Brookfield, 1827)

Distance (F-8) to (I-8): 8099.51' (Peirce 6/2/69, survey for I & M Electric line easement) 7990.23' (Marbach & Brady, 1995)

Distance (E-8) to (F-8): 2642.25' (Notes obtained from Prestine dated 3/13/89) 2642.05' (Marbach & Brady, 1995)

(Continued on reverse side)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument: Set concrete monument (36" long)/rebar with aluminum tablet, flush with ground. Tablet stamped "Cass County Remonumentation" and is accepted as a careful and faithful reestablishment of the original corner.

Accessories:

- Masonry nail set 4' high on top of 10" stump, N 1° W - 6.15'
Masonry nail in 4" Mulberry, S 90° E - 3.60'
Masonry nail in 4" Mulberry, S 1° W - 6.78'
Masonry nail in 6" Mulberry (18" Mulberry growing around it), S 90° W - 41.43'

Signed by [Signature]

Date Feb 12, 1997

Surveyor's Michigan License No. 37280

Grid table with columns A-L and rows 2-13. A triangle marker is located at the intersection of column H and row 8.

B. (Continued)

(G-8) established at 2642.05' East of (F-8)

(F-8) thru (I-8): iron pipes set (Peirce, 6/2/69)

(F-8): iron pipe found (Marbach, 1995)

(G-8), (H-8): Nothing found (Marbach & Brady, 1995)

(I-8): Rebar found (Marbach, & Brady, 1995)

(I-8) established as follows:

$[(F-8) \text{ to } (I-8)] - [(F-8) \text{ to } (G-8)]/2 = (7990.23' - 2642.05')/2 = 2674.09'$

(I-8): 2674.09' East of (H-8)

It follows then, that Distance (I-8) to (J-8): 2647.05' (Peirce 6/2/69)  
2647.25' (Marbach & Brady, 1995)

