

**Cass County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in NE corner, Section 13, Ontwa Twp.

<u>Cass</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>15W</u>	<u>M - 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-22-1999 12:50:48

Ann L. Simmons
REGISTER OF DEEDS

Register of Deeds Stamp & File
Number

Ratified by Peer Group
 In Accordance With P.A. 285
 Chairman Sue C. [unclear]
 Dec 7 1999

4. Lot No. _____, Recorded Plat _____
 5. Private Claims: _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

I, Daniel B. Zwar, in a field survey on Dec. 13,
 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of
 1970, the corner points mentioned in lines 1 and 2 above were in conformance
 with regulations and rules therefore as required in the current manual of survey
 instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and /or that the corner points
 mentioned in lines 3, 4 and 5 above were in conformance with the rules of the
 Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
 re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 - WM Brookfield - Set corner - 14" Y. Oak N 82 1/2° W 57 lks, 12" W Oak S 29° W 59 lks.

1996 - D.L. Kesler - Found unknown at post on fence to North - 6" wood fence corner .6" E & .6" S; 10" Elm N 40° W 8'; 4" Oak S
 87° E 24.10'; 10" Oak S 48° E 41.20'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 - D.B. Zwar - Found stone at E-W tree line and next to fence end post of fence to North, removed stone, found nothing else.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999 - D.B. Zwar - Set standard Cass County remon concrete monument to stone relocation.

Witnesses: Pk in the following:
 8" O. Orange N 87° W 14.93';
 12" O. Orange N 40° W 7.88';
 15" Oak S 56° E 41.33';
 12" Locust N 50° E 10.06';
 E 1/4 post Sec 12-8-15 North 2643.38';
 E 1/4 post Sec 13-8-15 South 2642.32';
 NW corner Section 18-8-14 South 207.79'.



This location is accepted as the best available evidence of the position of the original corner.

Signed by Daniel B. Zwar

Date Dec 22, 1999

Surveyor's Michigan License No. 28435

FEB 24 2000

SECTION