

**Cass County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Cass SE corner, Section 13, Ontwa Twp.

<u>Cass</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>15W</u>	<u>M - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-22-1999 12:51:26

Ann L. Simmons
REGISTER OF DEEDS

Register of Deeds Stamp & File
Number

Validated by Peer Group
In Accordance With P.A. 345
Chairman [Signature]
Date Dec 7, 1999

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Daniel B. Zwar, in a field survey on Dec. 15,
19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of
1970, the corner points mentioned in lines 1 and 2 above were in conformance
with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and /or that the corner points
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the
Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1827 - WM Brookfield - Ran South & set corner; 4" Hickory S 55 1/2° W 9 Lks; 18" Y. Oak N 23° W 82 Lks

1992 - CF Marbach - Set pipe NE gar corner S 15° E 5.95'; 1.5' W of N-S fence; 12" Elm N 5° W 24.12'; 20" Locust S 70 E 18.22';
805'W to iron pipe; 2618.36' West to S1/4 post Section 13.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 - D.B. Zwar - Found Marbach iron & witness but no other evidence of corner. This is on line from SW corner Section 18 Mason
to East 1/4 post Section 13 Ontwa.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999 - D.B. Zwar - Placed standard Cass remon concrete monument to Marbach iron location.

Witnesses: PK in 15" Elm S 75° E 21.52';
PK in P Pole (C592-78) N 02° E 49.42';
PK in 18" Elm N 10° E 24.48';
PK in 24" Locust S 22 E 39.62';
NE gar corner S 30° W 6.02';
SW corner Sec 18-8-14 South 197.26';
Iron pipe West 804.91';
S 1/4 Post Sec 13 West 2618.19';
E 1/4 Post Sec 13 North 2650.75'.



This location is accepted as the best available evidence of the position of the original corner.

Signed by Daniel B. Zwar

Date Dec 22, 1999

Surveyor's Michigan License No. 28435