

JAN 21 1999

SECTION

**CASS COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Liber **00003** Page **0179**

STATE OF MICHIGAN  
COUNTY OF CASS  
Recorded

12-10-1998 10:31:44

Ann L. Simmons  
REGISTER OF DEEDS

Rectified by Peer Group  
In Accordance With P.A. 345  
Chairman Dale C. Keen  
Date Oct. 29, 1998

For corners in

<u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey COMMON TO SEC 1, T8S, R17W (M-2)	T <u>8</u> R <u>16</u>	<u>A-2</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, V.J. Strebs, in a field survey on NOV 6, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S. SOUTH ON EAST SIDE OF SECTION 1, T8S, R17W MEASURED 40.00 CHAINS, SET POST 6" MAPLE NORTH 20 LINKS NO OTHERS HANDY.
- 1950'S US12. M.D.O.T. - QUARTER CORNER IS 1.95' NORTH AND 2.20' WEST OF SURVEY CENTERLINE OF NORTH BOUND LANE OF
- 1960 DREHER, MON. BOX 1.95' NORTH OF SURVEY CENTERLINE OF NORTH BOUND LANE. IRON NORTH 158.8'.
- 1961 R.W. PRESTINE MON. BOX 1.95' NORTH OF SURVEY CENTERLINE IRON WEST 175.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON ROD IN MONUMENT BOX IN NORTH BOUND LANE OF US 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET B.C.R.P. BRASS CAP IN 3/4" IRON, IN 1 1/4" IRON, SET OVER EXISTING 1" IRON ROD.  
WEST EDGE OF CONCRETE PAVEMENT N35° W - 9.58'  
EAST EDGE OF CONCRETE PAVEMENT S35° E - 12.45'  
SET REBAR - N15° E 25.89'  
SET REBAR - S60° E 31.40'  
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]  
Surveyor's Michigan License No. 26469



Date 2 DEC 1998