

JAN 21 1999

CASS COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF CASS Recorded

12-10-1998 10:31:12

Ann L. Simmons REGISTER OF DEEDS

Platified by Peer Group In Accordance With P.A. 345 Chairman Dale C. Sew Date Oct. 29, 1998

SECTION

For corners in

Table with columns: Located in: (County), Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, V. J. Strebs, in a field survey on MAY 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET IN ORIGINAL SURVEYS.

- AUGUST 3 & 4, 1885 ALBERT DREW (SURVEY IN SECTION 12, T8S, R17W) STONE AT WEST QUARTER CORNER OF SECTION 7, T8S, R16W, CASS COUNTY NORTH 32 1/2 LINKS. 1947 & 1948 H.L. DREHER - STONE NO WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/C.C.R.P. CAP ON TOP; WITNESS TAG IN 12" HICKORY S10° W 23.01'. WITNESS TAG IN 14" OAK S70° E 11.82'. WITNESS TAG IN 16" CHERRY N10° E 16.19'. B.C.R.P. MON. W/BRASS CAP SOUTH 20.75' THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by [Signature] Surveyor's Michigan License No. 26469



Date 2 DECEMBER 1998