

CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **MILTON TOWNSHIP**

| | | |
|---------------------------------------|--------------------------|---------------|
| <u>CASS</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>8S</u> R <u>16W</u> | <u>A-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-22-1999 12:36:56

Ann L. Simmons
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Ratified by Peer Group
In Accordance With P.A. 845
Chairman *[Signature]*


I, **CHRISTIAN F. MARBACH**, a field survey on **DECEMBER 7**, 19**99**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

POST, W. M. BROOKFIELD D. S. 1827
40.84 CHAINS INTERSECTED INDIANA STATE LINE 3.4 CHAINS
EAST OF MILE POST 31.
W. OAK 7" N 61°W 51
Y. OAK 10" N35°E 27



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STANDARD CASS COUNTY MONUMENT, ALUM. CAP & ALUM. ROD WITH MAGNET IN
MON. BOX
USED CORNER AS SET SEVERAL TIMES, ALSO USED BY OTHERS AND RATIFIED BY BERRIEN
COUNTY PEER GROUP 11-8-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

USED SAME CORNER AS ABOVE, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION
OF THE POSITION OF THE ORIGINAL CORNER.
NAIL & WASHER IN 16" HICK. S12°W 30.89' 12' + N OF CL STATE LINE ROAD AS CONSTRUCTED
NAIL & WASHER IN ELEC. & TEL. POLE N21°W 7.34' E-W CHAIN LINK FENCE S 36.50'
NAIL & WASHER IN 26" HICK. N32°E 42.48' STEEL FENCE POST NORTH 10.1'
NAIL & WASHER IN 14" CEDAR N72°E 45.15'

Signed by *[Signature]* Date 12/21/99

Surveyor's Michigan License No. 37280

FEB 24 2000

SECTION