

**CASS COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **MILTON TOWNSHIP**

<u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>16W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF CASS  
Recorded  
12-22-1999 12:38:10  
Ann L. Simmons  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

Ratified by Peer Group  
 In Accordance With P.A. 345  
 Chairman *[Signature]*

I, **CHRISTIAN F. MARBACH** in a field survey on **DECEMBER 7,** 19 **99**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**ORIGINAL MONUMENT: NOTHING SET**  
**SUBSEQUENT RESTORATION: IDENTIFIED BY WITNESS, MARKED BY SELF**  
**FOUND POST-BOTH WITNESSES CUT, SET STONE ABOVE WEST OAK POST**  
**HICKORY 11" N 83 1/4°W 47 1/2 LINKS (AMOS SMITH 10/4/1882)**  
**FOUND STONE WITH CUT (HARNER 1977)**  
**SET CONCRETE MONUMENT (ABONMARCHE 1994)**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**FOUND CONCRETE MONUMENT**

FEB 24 2000

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**MONUMENT: CONCRETE MONUMENT (36" LONG/REBAR WITH ALUM. TABLET) TABLET IS STAMPED "CASS COUNTY REMONUMENTATION". THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.**

- PK IN NORTH SIDE 18" CHERRY S88°W 26.70'
- PK IN EAST SIDE 8" SASSAFRASS N80°W 15.00'
- PK IN WEST SIDE 8" SASSAFRASS N0°E 9.6'
- PK IN SOUTH SIDE 28" CHERRY N89°E 31.2'

Signed by *[Signature]*  
 Surveyor's Michigan License No. **37280**

Date 12/24/99