

**CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **MILTON TOWNSHIP**

<u>CASS</u> (County)	Located In:	Corner Code \neq
1. Public Land Survey	T <u>8S</u> R <u>16W</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
COUNTY OF CASS
Recorded
12-22-1999 12:38:21
Ann L. Simmons
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

Ratified by Peer Group
 In Accordance With P.A. 245
 Chairman *[Signature]*

CHRISTIAN F. MARBACH in a field survey on DECEMBER 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**ORIGINAL MONUMENT: SET POST CORNER TO FRACTIONAL SEC. 20 & 21, 7.30 CHAINS
E. OF 33rd MILE POST (BROOKFIELD, 1828)**
**ACCESSORIES: 9" HICKORY N 62° W 21 LINKS
7" HICKORY N 82° E 65 LINKS**
**SUBSEQUENT RESTORATION: SET STONE OVER POST (F. E. SMITH 1897)
12" OAK N 49 5/6 E 75 LINKS
7" OAK N 19 W 22 3/4 LINKS
1" IRON PIPE SET (ABONMARCHE 1994) (LCRC 2, PAGE 334)**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1" IRON PIPE FOUND AS DESCRIBED ABOVE

RF

FEB 24 2000

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MONUMENT: CONCRETE MONUMENT (36" LONG/REBAR WITH ALUM. TABLET) TABLET IS STAMPED "CASS COUNTY REMONUMENTATION", AND THIS IS ACCEPTED AS A CAREFUL AND RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

**PK IN NORTH SIDE 12" SASSAFRASS S 89° W 5.33'
PK IN EAST SIDE 8" SASSAFRASS N 1° W 8.20'
PK IN SOUTH SIDE 8" SASSAFRASS S 45° E 7.30'
CONCRETE MONUMENT S0° E 3.3'
IRON PIPE IN MON. BOX E-7 N 0°E 2790.39'**

Signed by *Christian Marbach* Date 12/21/99
Surveyor's Michigan License No. 37280