

CASS COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MILTON TOWNSHIP

| CASS (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>8S</u> R <u>16W</u> | <u>K-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-22-1999 12:40:06

Ann L. Simmons
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Notified by Peer Group
In Accordance With P.A. 345
Chairman

I, **CHRISTIAN F. MARBACH** in a field survey on **DECEMBER 8**, 19 **99**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL MONUMENT: SET POST CORNER TO FRACTIONAL SEC. 23 & 24 10.13 CHAINS EAST OF 36th MILE POST (BROOKFIELD, 1828)

**ACCESSORIES: 9" YELLOW OAK N 11° W 36 LINKS
8" WHITE OAK N 14° E 66 LINKS**

**SUBSEQUENT RESTORATION: FOUND IRON OVER STONE (MICHIANA SURVEYORS, 1976)
FOUND 5/8" IRON (WIGHTMAN-PEIRCE INC, 1987) PP N 45°W 25' FEE POST
S 45° E 12.35'
FOUND 5/8" IRON (WIGHTMAN-PEIRCE INC, 1989) " " "
FOUND 5/8" IRON (WIGHTMAN-PEIRCE INC, 1993) " " "
2" PIPE EAST 5.4', PK NORTH 330.00'**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NOTHING FOUND AT THE CORNER, FOUND 2" REFERENCE PIPE 5.4' EAST. SET NEW POST 5.4' WEST OF FOUND 2" PIPE AS SHOWN ON WIGHTMAN-PEIRCE SURVEYS.

FEB 24 2000

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

CONCRETE MONUMENT (36" LONG/REBAR WITH ALUM TABLET) TABLET IS STAMPED "CASS COUNTY REMONUMENTATION", AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

**NE CORNER METAL BLDG. S 25° W 53.5'
PK IN SOUTH SIDE 10" WILD CHERRY n 89° W 8.4'
IRON PIPE FOUND EAST 5.4'
PK IN NORTH SIDE 24" OAK S 75° E 42.0'**

Signed by *Christian Marbach*

Date *12/21/99*

Surveyor's Michigan License No. **37280**