

**SURVEY & REMONUMENTATION**

FEB 19 1998

Liber **00003** Page **0141**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**CASS COUNTY REMONUMENTATION**

For corners in <u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey MILTON TOWNSHIP	T <u>8S</u> R <u>16W</u>	<u>L-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-26-1997 12:00:06

Ann L. Simmons  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Ratified by Peer Group  
 In Accordance With P.A. 345  
 Chairman Dale L. Kesler

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, DALE L. KESLER, in a field survey on Oct. 20, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- \*1827 WILLIAM BROOKFIELD. SET POST. WITNESSES: 8" OAK n 9 3/4 DEGREES E 41 LKS., 15" OAK N 48 1/4 DEGREES W 106 LKS.
- \*MAR. 9, 1880 AMOS SMITH. IDENTIFIED BOTH WITNESSES GOOD. FOUND STONE. WITNESSES: 24" OAK N 19 3/4 DEGREES W 94 1/2 LKS., 13" OAK S 50 DEGREES W 68 LKS.
- \*SEPT. 1978 ROBERT PRESTINE. FOUND STONE SET BY F.E. SMITH, 1879. WITNESSES: 10" CHERRY N 25 DEGREES W 22.0', 6" CHERRY S 65 DEGREES E 21.0', 24" CHERRY 30 DEGREES W 33.7'.
- \*NOV. 29, 1978 DOUGLAS PEIRCE. FOUND STONE USED BY A. SMITH, MARCH 9, 1880, SEE BOOK D, PG 147-148, L.C.R.C. LIBER 2, PAGE 147. SET STANDARD MONUMENT 6" BELOW GRADE. WITNESSES: 2" SASSAFRAS S 2 DEGREES W 22.10', 8" CHERRY N 30 DEGREES W 10.25'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STANDARD MONUMENT OVER STONE. THE ACCESSORIES OF THE SEPTEMBER 1978 SURVEY DONE BY BOB PRESTINE VERIFY LOCATION OF THE STONE. ACCEPTED STANDARD MONUMENT OVER STONE AS BEST EVIDENCE OF CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CONCRETE MONUMENT WITH ALUMINUM CAP IN PLACE OF STANDARD MONUMENT NEXT TO STONE THAT WAS MOVED TO THE WEST AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.  
 NAIL & TAG 8" CHERRY N 30 DEGREES 10.25'  
 NAIL & TAG 10" CHERRY N 25 DEGREES W 22.8'  
 NAIL & TAG 24" CHERRY S 30 DEGREES W 33.70'  
 NAIL & TAG 6" CHERRY S 65 DEGREES E 21.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Dale L Kesler

Surveyor's Michigan License No. 38117

Date 12/4/97

