

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. <u>3</u> R. <u>2</u> E. <u>W</u>	A-1 a Meander corner, on West side, Sec. 6
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/28 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Meander Corner, on West side, Sec. 6, set originally by Austin Burt, D.S. in 1840.

A Cedar 10" was marked for the Meander Corner.
Bearing:
Spruce 8" 170°W 10 Links

Meander Corner recorded as 35.73 chs. South of Twp. Corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Found a 5/8" Iron and Cedar Post, set by G.F. DeLaMater, R.L.S. in 1947. Found witness, marked at that time. Reviewed his actual field notes to assist in locating this Meander Corner.

Found a 10" Cedar, blazed and scribed about 1956. This tree lies, 15.6' East and 20.0' South of DeLaMaters' Corner. Age of blazes determined by count of annual growth rings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Recorded corner as set by DeLaMater. Found a Cedar, now 11" in diameter, Bearing S53°E 32.3'. Found blaze with scribe marks "NBT" and a penny-size disc, tacked thereon. Age of marks determined by count of annual growth rings.

SIGNED BY Billy D. Buckler DATE 9/13/72
BILLY D. BUCKLER

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)