

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Chippewa COUNTY


T 42.4 R 2-3E

DESCRIPTION OF CORNER Meander corner bet. secs. 36-31 on south shore of Big Trout Lake

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10-26-71

WITNESSES TO CORNER..... 7" W. Birch (M.C. NBT) S7°E 16.0'



8" W. Birch (M.C. NBT) S61°W 22.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a cedar stump, 3½' high, bearing S12°E, 24 lks. Found bottom blaze, notch and scribe marks and part of top face. Corner found with survey crew while making retracement survey to north.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

Billy D. Buckler

DATE 12-7-71

REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68