

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 41 .. NR. 5 East ..

Chipewea  
Drummond Island .. COUNTY

DESCRIPTION OF CORNER .. 1/4 cor. between secs: 3-10 ..

DESCRIPTION OF CORNER MONUMENT .. 1" Pipe with 4" Brass Cap ..

WITNESSES TO CORNER .. 10" Cedar (1/4s NBT) N24° E 19 Lks. ..

12" Cedar (1/4s NBT) N57° W 70 Lks. ..

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Replaced 1/4 cor. from two Cedar B.Ts. bearing N8°E 11 Lks., tree  
down, has been chopped out, overgrowth scars plain. Cedar S35°W  
6 Lks. down and in poor condition. Cor. shown to us by Carl  
Schultz, Hermansville, Michigan. Found Cedar tree near used by  
several Cruisers among names is N. Trombley 1938. Cor. lies  
41 Lks. north and about 3 chs. east of cor. set by Beaudry, Co.  
Surveyor. Cor. placed and wit. 8/1/58.

SURVEYORS SEAL

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 7/30/59  
REGISTERED LAND SURVEYOR