

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>5E</u>	<u>E3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3					●								
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/11/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E3) Corner common to Sections 4-5-8-9. 1845 - Established by John Mullett Deputy Surveyor, 80.00 chains south of Section corner E1. Set post. Pine 20" N22E 16 links, Fir 8" S35W 20 links. 1974 - G.R.Gabel RLS notes in a diagram on the reverse of a recorded Land Corner Recordation Certificate dated Nov. 28, 1974 that he found a 1.5" pipe and gives distances to monumented E1 5304.46' northerly and to a monumented MC 4126.42' westerly.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E3) Found a 1.5" dia. iron pipe in good condition 5298.49' southerly from Section corner E1 and 4123.59' easterly from G.R.Gabel's monumented MC between Sections 5 and 8. I accepted the monument as the best available evidence of the position of the original corner and replaced it with a new monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Tamarack S40W 85.3' mrkd "S8 NBT"
 12" Sugar N74W 54.2' "S5 NBT"
 5" Balsam S84W 51.6' "S8 NBT"
 Spike in 8" spruce stump S73E 23.87'
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/27/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division