

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T <u>41N</u> R <u>5E</u>	<u>MC W. of D3</u>
2. Property Controlling in Section	S <u>5</u> T <u>41N</u> R <u>5E</u> S _____ T _____ R _____ S _____ T _____ R _____	<u>4</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		MC		8		9		10		11		12
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 5) Northwest 1/16 corner, Section 5. 1974 - Established by G.R.Gabel RLS at the intersection of 1/16 lines. Set 3"x4" alum. plate on a 1" dia. steel rod 30" long. Spruce 7" N86E 7.9', Cedar 3" S15E 21.7', Birch 3" N21W 8.5'. This corner subsequently used in 1986 by Eino Sainio RLS to subdivide the SE1/4 of the NW1/4 of Section 5.

(MC W. of D3) Previously recorded as the Meander Corner between Sections 5 and 8 on the shore of Lake Huron. 1974 - G.R.Gabel set a 3"x4" alum. plate on a 30" long rod 16" out of ground. Birch 10" North 0.5', Cedar 7" S15E 14.6', Cedar 4" N82E 24.5'. This corner has been used to control subsequent surveys by others.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 5) Found the 1974 monument of record, as described, in good condition, and at substantial record bearing and distance from the 1974 Spruce and Cedar BTs, both in good condition. Verified that the monument is substantially at the position of the intersection of straight lines connecting opposite 1/16 corners and accepted same as a careful and faithful establishment of the position of the corner.

(MC W. of D3) Found the 1974 monument of record, in good condition, and at substantial record bearing and distance from the two 1974 Cedar accessories, both in good condition. The 1974 Birch BT was not recovered. Left the monument in place and made new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Fd. 3"x4" alum. plate on 1" dia. steel rod. Set measuring nail with MDNR tag in the side of:  
 10" Spruce S85E 8.1' mrkd "NW1/16" (1974 BT)  
 8" Cedar S06E 21.75' do do  
 8" Tamarack S61W 44.6' mrkd "NW1/16 BT"  
 Power Pole N01W 61.95'  
 Bearings are magnetic.

(MC) Fd. 3"x4" alum. plate on 1" steel rod. Set measuring nail with MDNR tag in the side of:  
 8" Cedar East 24.8' mrkd "MC" (1974 BT)  
 14" Cedar S10E 14.5' do do  
 12" Cedar N57E 4.8' mrkd "MC BT"  
 5" B.Spruce S62W 7.9' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/27/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

