

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>5E</u>	<u>E2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 03/22/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E2) Quarter corner common to Sections 4 and 5. 1845 - Established by John Mullett Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Tamarack 10" S80W 185 links, Fir 8" N88W 169 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E2) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between monumented Section corners of record 2649.24' north and south. I note that this position, calculated but not monumented by G.R.Gabel RLS, was used to subdivide Section 5 in a 1974 survey which established numerous interior 1/16 corners, as well as the Center of Section 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 18" Cedar S60W 2.35' mrkd "1/4S NBT"
 9" Cedar N35W 24.3' do
 5" Cedar South 24.2' do
 9" Cedar S55E 16.5' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 07/27/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division