

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>5</u> T <u>41N</u> R <u>5E</u>	<u>D2</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5			●		4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/09/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D2) Center of Section 5. Not established in the original survey. 1974 - Established by G.R.Gabel RLS. Set a 3"x4" alum. plate on a 1.5" dia. pipe 24" out of ground. Spruce 11" S13W 30.3', Birch 3" S42E 8.1', Birch 3" N19W 41.4'. Though Mr. Gabel does not state how he arrived at the position for the corner, calculations using his measurements of record prove that he established the position at the intersection of straight lines connecting opposite 1/4 corners. This corner was used in the further subdivision of Section 5 in 1974, 1986, and 2003 by Mr. Gabel and Eino Sainio RLS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D2) Found the 1974 monument as described, in good condition, and in accord with Mr. Gabel's survey of Section 5. The 1974 witnesses were not recovered. Accepted the corner as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D2) Fd. 3"x4" alum. plate on 1.5" Iron Pipe.
 Set measuring nail with MDNR tag in the side of:
 6" B.Spruce N06E 12.9' mrkd "CS BT"
 4" Balsam S77E 16.95' do
 12" B.Spruce S16E 40.15' do
 4" W.Birch S70W 46.0' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/27/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division