

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 41N R 5E	C2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

I, Stephan J. Szyszkoski, in a field survey on 03/16/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C2) Quarter corner common to Sections 5 and 6. 1845 - Established by John Mullett Deputy Surveyor 40.00 chains south of Section corner and 21.71 chains north of the Meander Corner on the margin of Lake Huron. Set post. Fir 6" N27E 17 links, Spruce 6" S22W 16 links. 1974 - Remonumented by G.R.Gabel RLS, who found no evidence of the position of the original corner. Set 3"x4" alum. plate on a steel rod. Spruce 4" S76W 13.5', Spruce 1.5" S12E 27.4', Spruce 3" S65E 23.2'. Mr. Gabel used this corner to subdivide Section 5. 1986 and 2003 - This corner used to control surveys in Section 5 by Eino Sainio RLS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C2) Found the 1974 monument as described, in good condition, and at record bearing and distance from the Spruce NBTs S76W and S12E. The Spruce S65E is gone. Accepted the monument as a reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C2) Found 3"x4" alum. plate on 1" sq. steel rod.  
 Set measuring nail with MDNR tag in the side of:  
 4" Cedar S54W 2.4' mrkd "1/4S NBT"  
 6" Cedar N44W 7.75' do  
 6" Cedar S44E 13.1' do  
 6" B.Spruce S03E 27.15' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/27/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division