

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 5E	MC S.of C2
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S T _____ R _____	_____
	S 5 T 41N R 5E	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7					8		9		10		11	12
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on MC 5 03/23/2010 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC S. of C2) Previously recorded as the Meander Corner between Sections 5 and 6 on the shore of Lake Huron. 1974 - Monumented by G.R.Gabel RLS. Found a 1/2" reinforcing bar in concrete at edge of water is [sic] a corner to the Ella B. Hudson Plat of 3rd Point of Whitney Bay. Set a 3"x4" alum. plate on a 1.5" dia. steel rod 27" long 1" out of ground. Cedar 6" N33W 30.4', Cedar 5" N10E 33.9', Cedar 6" S48W 39.6'. This corner position has been used for several surveys within Section 5 since 1974, and within Section 6 since 1953, the date of the Ella B. Hudson plat, surveyed by T.L.Jackson.

(5-Sec. 5) North 1/16 corner, Section 5. Not established in the original survey. The position for the corner was calculated by G.R.Gabel RLS in 1974 and used to subdivide the NW1/4 of Section 5. Mr. Gabel used a position midway and on a straight line between the Center of Section 5 and the unmonumented North 1/4 corner of Section 5.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC S. of C2) Found the 1974 monument as described, in good condition, and at substantial record bearing and distance from the Cedar accessories, all in place and in good condition. Left the monument in place and made several new accessories, as described below.

(5-Sec. 5) Found no monumentation at the corner position. Established the corner midway and on a straight line between the Center of Section 1331.17' south and the North 1/4 corner 1331.17' north. The North 1/4 corner, being in Jackson Lake, is unmonumented. Its position is midway between the NW and NE corner of Section 5. The position for this 1/16 corner checks well with Center D2 and with 1/16 corner #4, both monumented by Mr. Gabel in 1974.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Found 1" steel rod w/3"x4" alum. plate. Set measuring nail with MDNR tag in the side of:
 9" twin Cedar S51W 39.55' unmarked
 12" Cedar N21E 34.7' do
 N22W 7.6' to NE corner of a building
 S60W 10.15' to SE corner of same building
 Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" W.Birch S76E 23.55' mrkd "N1/16 BT"
 14" Cedar S16E 46.8' do
 7" Cedar S56W 23.45' do
 14" Cedar N29W 26.55' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 07/27/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

