

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X</u> , R. <u>6</u> E. <u>X</u>	<u>L-1, K-2</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David L. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-22 & 7-21, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1 1/4 cor. on North side of sec. 1. Wood Post, Cedar 9", N15°E, 22 lks. & Cedar 12", N21°W, 20 lks.
- 2 West 1/4 cor. of sec. 1. Wood Post, Cedar 6", N45°E, 22 lks. & Aspen 6", S46°E, 6 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1 Corner set from 2 OBT'S, Cedar 9" N15°E, 22 lks. & Cedar 12", N21°W, 20 lks. Both trees are down out faces and notch plain.
- 2 Set M.F.C.L. between the NW and SW sec. cors. of sec. 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------------|------------------------------------|
| -1 D.N.R. Monument. New Bearings: | K-2 D.N.R. Monument. New Bearings: |
| 12" Cedar, N04°W, 34.0' | 10" W. Birch, N29°E, 27.8' |
| 8" Cedar, East, 8.1' | 4" Spruce, S50°W, 9.7' |
| 7" Cedar, S32°E, 24.0' | 6" Balsam, N22°W, 43.0' |
| 6" Cedar, NE, 21.0' | 10" Spruce, S18°E, 21.15' |

SIGNED BY

David L. Babbitt
David L. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

DATE