

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Chippewa Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. <u>X</u> R. <u>6</u> E. <u>X</u>	<u>M-1a, L-2</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. <u>X</u> R. _____ E. <u>X</u>	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**M-1a** Meander Corner on North side of sec. 1, lies on West shore of Dry Lake. Fir 8" for Meander Corner.

**L-2** Center of Section 1. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**M-1a** Found old sq. Cedar Post on the West shore of Dry Lake. It is not of record but it does fit the meander record for meanders of Dry Lake and is nearly on line between the N.E. section corner of section 6, T41N R7E and the North 1/4 corner of section 1 of this township. Both of which were set from O.B.T.S. SEE SKETCH ON BACK OF PAGE

**L-2** Corner set at intersection of North and South and East and West 1/4 lines of section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**M-1a** D.N.R. Monument. New Bearings: 4" Cedar, S60°E, 4.4' & 5" Cedar, N09°W, 17.2' & 6" Cedar, N42°W, 43.5' & 6" Cedar, S29°W, 23.8'.

**L-2** D.N.R. Monument. Bearings: 6" H. Maple, N72°E, 11.0' & 5" H. Maple, S03°W, 7.7' & 8" H. Maple, S82°E, 16.1' & 6" H. Maple, S50°W, 12.6'.

SIGNED BY David E. Babbitt  
David E. Babbitt

DATE 1-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: