

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. S. R. <u>6</u> E. W.	<u>M-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>12</u>	, T. <u>41</u> N. S. R. <u>6</u> E. W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-3, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-4 East 1/4 corner of Sec. 12. Beech 12" marked for corner in original survey. Record obtained from Eino Sainio R.L.S. 2" O.D. Pipe 41" long, 7" H. Maple, N4°W, 14.0' and 6" H. Maple, N85°E, 34.5'.

7 North 1/16 corner on east side of sec. 12. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-4 Found both N.E.T.'s noted in survey records from Eino Sainio R.L.S. The pipe was not in place. Set new pipe from his N.E.T.'s.

7 Corner set M.P.O.L. between East 1/4 cor. and Northeast sec. cor. of section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Buried 1" pipe with Plastic R.L.S. Cap. New Bearings:

8" H. Maple, N71°E, 43.6' and 8" H. Maple, S46°E, 36.5' and
14" R. Maple, N63°W, 37.4' and 14" R. Maple, N35°W, 16.5'.

7 Buried 1" pipe with Plastic R.L.S. Cap in road. Bearings: .

7" H. Maple, S71°E, 20.4' and 14" H. Maple, S33°E, 29.8' and
14" H. Maple, N72°W, 43.7' and 6" Ironwood, S88°W, 28.7'.

SIGNED BY

David B. Babbitt

DATE 1-24-83

David B. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: