

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. S. R. 6 E. W.	K-1
2. PROPERTY CONTROLLING IN SECTION	2, T. 41 N. S. R. 6 E. W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

David E. Babbitt

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 Northwest corner of section 1. OBT'S Wood Post, Tamarack 10", S56°W, 4 links & Tamarack 10", S52°E, 26 links.
- 2 East 1/16 corner on North side of section 2. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-1 Set by single proportionate measurement between the North 1/4 corner of Section 1 and the North 1/4 corner of section 2.
- 2 Set corner M.P.O.L. between North 1/4 corner and Northeast section corner of sec. 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 D.N.R. Monument. New Bearings: 6" Dead Cedar, N72°E, 6.9' & 6" Dead Cedar, S37°E, 10.8'
6" Dead Cedar, S62°W, 13.1' & 6" Dead Cedar, N55°W, 10.6'
Grader Blade, S86°E, 61.97'.
- 2 D.N.R. Monument. Bearings: 8" Cedar, N18°W, 36.4' & 8" Cedar, S69°W, 4.5' & 6" Cedar, S4°E, 13.7' & 14" Spruce, S86°E, 8.0' & Grader Blade, N84°W, 26.0'.

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 1-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)