

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROL- 1 ING IN SECTION_____	, T. 41 N. S., R. 6 E. W.	16, 9, 14
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David b. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 11-3 & 4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 16 East 1/16 corner on South side of section 1. Not prev. est.
- 9 East 1/16 corner of section 1. Not prev. est.
- 14 South 1/16 corner on East side of section 1. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16 Corner set M.P.O.L. between South 1/4 corner and Southeast section corner of section 1.
- 9 Corner set M.P.O.L. between center corner and East 1/4 corner of section 1.
- 14 Corner set M.P.O.L. between East 1/4 corner and Southeast section corner of section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 16 D.N.R. Monument. Bearings: 16" R. Maple, N82°E, 17.85' & 10" R. Maple, N31°E, 6.3' & 6" H. Maple, S74°E, 3.0' & 6" H. Maple, N77°E, 8.1'.
- 9 D.N.R. Monument. Bearings: 12" W. Birch, N89°E, 27.9' & 8" W. Birch, S74°E, 37.2' & 16" Cedar, S73°W, 25.1' & 12" W. Pine, N50°E, 67.9'.
- 14 D.N.R. Monument. No witness available. Old Stone Fence East and West, 105.2' South.

SIGNED BY

David E. Babbitt

DATE

1-24-83

David E. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)