

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. 2 Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. S., R. <u>7</u> E. W.	<u>E-1, A-1a</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-19-83 & 11-3-82, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-1** North 1/4 corner of section 6. O.B.T.'S Cedar 8" for 1/4 corner and Aspen 9", N26°W, 16 lks.
- A-1a** Meander Corner on North side of sec. 6. Corner lies on East shore of Dry Lake. O.B.T.'S Fir 6" for corner & Cedar 12", S64°E, 22 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1** Corner set by single proportionate measurement between Meander Corner East side of Dry Lake and NE corner of section 6.
- A-1a** Found old squared cedar post on the East shore of Dry Lake. It is not of record but it does fit the meander record for meanders of Dry Lake, and is nearly on line between the North 1/4 corner of section 1, T41N R6E and the N.E. corner of section 6 of this township. Both of which were set from O.B.T.S. SEE SKETCH ON BACK OF PAGE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-1** 1" pipe 32" long with Plastic RLS Cap. New bearings: 8" Cedar, N89°E, 11.2' and 6" Cedar, S20°E, 43.7' and 8" Cedar, S23°W, 25.8' and 7" Cedar, S78°W, 51.4'.
- A-1a** D.N.R. Monument. New Bearings: 4" Cedar, S9°E, 20.2' and 5" Cedar, S87°E, 30.8' and 7" Cedar, N57°E, 37.0' and 7" Cedar, N22°E, 31.5'.

SIGNED BY

David E. Babbitt
David E. Babbitt

DATE 1-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: