

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | 1 Corner LOCATED IN-- | Chippewa Co. CORNER CODE NUMBER |
|---------------------------------------|---------------------------------------|------------------------------------|
| 1. PUBLIC LAND SURVEY | T. <u>41</u> N. S., R. <u>6</u> E. W. | <u>C-5a</u> |
| 2. PROPERTY CONTROLLING IN SECTION | T. _____ N. S., R. _____ E. W. | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-29, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-5a M.C. on East side of Vanio Lake between sections 8 and 17. A Tamarack 8" for corner no B. T.'s marked.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-5a Found 9" Tamarack with definite blases healed over on all four sides. Tree is dead and broken off about 3 ft. above ground by the wind. Meaders of lake shore fit this location well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D. N. R. Monument placed at corner. Bearings: 6" Cedar, N51°E, 11.5'
 7" Cedar, N32°E, 20.9'
 4" Cedar, N82°E, 10.1'
 6" Cedar, S70°E, 12.9'

SIGNED BY

David B. Babbitt

DATE 5-14-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES.