

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA CO.

2 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S. R. <u>6</u> E. W.	<u>B5A, G-7</u>
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-7-85 & 10-15, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B5A Wit. Cor. to M.C. Between Sec's. 7-18 on West side of Pat's Lake. Corner set by Billy D. Buckler, R.L.S. on 7-30-58. 8" Cedar, N20°W, 24 lks. & 10" Cedar, S22°W, 39 lks.
- G-7 S.W. Section Corner of Section 15. O.B.T.'S: W. Pine 12, S02°W, 89 lks. & W. Pine 10, S20°E, 1.15 chs.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-5A Marked new witt. at corner set by Billy D. Buckler, R.L.S. 7-30-58 from O.B.T.
- G-7 Corner set from one O.B.T a 10" W. Pine Stump lower notch and upper scribe marks visible. Also a stump bearing S2°W, 58.74' no marks visible. Corner fits well with Lake to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR monument at both corners.

- B-5A 8" Cedar, N20°W, 15.84' & 10" Cedar, S22°W, 25.74' & 8" Cedar, N66°W, 18.3' & 10" Cedar, S84°W, 29.05'.
- G-7 8" W. Pine, S21°E, 31.7' & 10" W. Pine, S75°W, 23.6' & 12" R. Pine, N53°W, 45.6' & 10" Cedar, N50°E, 38.4', 10" W. Pine Stump OBT, S20°E, 75.9'.

SIGNED BY

Gerald L. Wiggins
Gerald L. Wiggins

DATE 9-9-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

