

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
CHIPPEWA CO. 3 CORNERS.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. X R. 6 E. W	H-5
2. PROPERTY CONTROLLING IN SECTION _____	10 T. 41 N. X R. 6 E. W	7, 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-13 & 10-14, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- H-5 South 1/4 Corner of Section 10. OBT'S: Birch 4", S51°W, 17 lks. & Birch 4", N68°E, 16 lks.
 - 7 North 1/16 Corner on the East side of Section 10. Not prev. set.
 - 15 West 1/16 Corner on the South side of Section 10. Not prev. set.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-5 Corner set M.P.O.L. between S.W. & S.E. Corners of Section 10.
 - 7 Corner set M.P.O.L. between N.E. Section Corner & East 1/4 Corner of Section 10.
 - 15 Corner set M.P.O.L. between S.W. Section Corner & South 1/4 Corner of Section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 DNR Monuments placed at all three corners.

H-5 12" W. Pine, N48°E, 38.70'	7 4" Cedar, S10°E, 8.9'	15 8" W. Pine, S80°E, 44.35'
12" Cedar, S75°W, 10.70'	8" Cedar, S83°W, 20.3'	9" R. Pine, S47°E, 30.05'
10" Cedar, South, 28.20'	4" Cedar, N64°W, 22.3'	10" Cedar, S02°E, 42.70'
8" Cedar, S33°E, 48.70'	8" Cedar, S81°E, 25.5'	6" R. Pine, S78°W, 43.70'
	Center Line Road, East 14.1'.	

SIGNED BY Gerald L. Wiggins DATE 5-18-87
 Gerald L. Wiggins
 SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

