

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA CO.

3 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> <del>XX</del> N. R. <u>6</u> <del>XX</del> E.	<u>G-3, G-4, G-5</u>
2. PROPERTY CONTROLL- ING IN SECTION_____	, T. _____ S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-13, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-3 N.W. Section Corner of Section 10. OBT'S: Beech 10", N72°E, 14 lks. & Beech 6", S62°W, 13 lks.
- G-4 West 1/4 Corner of Section 10. OBT'S: W. Pine 12", N20°E, 39 lks. & Tamarack 3", S15°W, 20 lks.
- G-5 S.W. Section Corner of Section 10. OBT'S: W. Pine 14", S71°E, 32 lks. & W. Pine 12", S34°W, 24 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Corner set by double proportionate measure between 1/4 Corner 1/2 mile North and Section Corner 2 miles South, and Section Corners 1 mile East and West.
- G-4 Corner set M.P.O.L. between N.W and S.W. Section Corners of Section 10.
- G-5 Corner set by double proportionate measure between Section Corners 1 mile North, East, and South and a Original Meander Corner to the West on East side of Vanio Lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


**DNR MONUMENTS PLACED AT ALL THREE CORNERS.**

- |                              |                                |                               |
|------------------------------|--------------------------------|-------------------------------|
| G-3 14" Spruce, N28°E, 58.0' | G-4 12" W. Pine, S48°W, 19.30' | G-5 14" R. Pine, N74°E, 5.45' |
| 5" Ironwood, S36°E, 28.95'   | 10" W. Pine, S30°E, 49.15'     | 10" Cedar, N38°E, 36.55'      |
| 8" H. Maple, S57°W, 39.45'   | 10" W. Pine, N43°E, 12.55'     | 14" R. Pine, N75°W, 17.60'    |
| 6" H. Maple, N70°W, 18.0'    | 14" R. Pine, N53°W, 24.75'     | 12" Cedar, S32°W, 36.48'      |

SIGNED BY Gerald L. Wiggins  
Gerald L. Wiggins

DATE 5-18-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521



FOR STATE AND UNITED STATES AGENCIES: