

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA CO.

3 CORNERS

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> N. <u>X</u> , R. <u>6</u> E. <u>X</u>		C-4 & 14, C-5, C-2
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-18, 5-19, 1987, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- C-4 & 14 Meander Corner on East side of Section 7 on South side of Pats Lake. OBT: 8" Tamarack.
- C-5 S.E. Corner of Section 7. OBT'S: Pine 6, N76°W. 5 lks. & Aspen 6, N55°E, 22.1ks.
- C-2 East 1/4 Corner of Section 6. OBT'S: Cedar 6, N24°W, 16 lks. & Fir 10", S45°E, 20 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-4 & 14 Corner set on the South side of Pats Lake and on a line from the N.E. Cor. of Sec. 6 and the S.E. Cor. of Sec. 7. (S.E. Cor. of Sec. 7 established by single proportionate measure between original M.C. on West side of Pats Lake and original M.C. on East side of Vanio Lake and record distance South from South side of Pats Lake). Distance across lake to North fits record.
- C-5 Corner set by single proportionate measure betw. orig. M.C. on West side of Pats Lake and orig. M.C. on East side of Vanio Lake and record distance South from South side of Pats Lake. Distance across Pats Lake to the North fits record.
- C-2 Cor. set M.P.O.L. between N.E. Corner and S.E. Corner of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR MONUMENTS PLACED AT ALL THREE CORNERS.

- | | | |
|---------------------------------|-----------------------------|---------------------------|
| C-4 & 14 6" Cedar, S43°W, 20.2' | C-5 14" Cedar, S65°E, 25.9' | C-2 7" Cedar, N50°W, 7.1' |
| 6" Cedar, S11°E, 19.85' | 8" Cedar, S21°W, 35.4' | 8" Cedar, N16°E, 18.3' |
| 6" Cedar, S58°E, 15.1' | 9" Cedar, N55°W, 18.25' | 14" Cedar, S87°E, 20.7' |
| 6" Tamarack, S89°E, 42.2' | 8" Cedar, N27°W, 20.5' | 10" Cedar, S48°E, 19.6' |

SIGNED BY Gerald L. Wiggins
Gerald L. Wiggins

DATE 5-26-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

