

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA

3 CORNERS

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. <u>SE</u> R. <u>6</u> E. <u>W</u>	<u>H-3, I-4</u>
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>41</u> N. <u>SE</u> R. <u>6</u> E. <u>W</u>	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-14, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-3 North $\frac{1}{2}$ Corner of Section 10. OBT'S: Sugar 7, N74^oE, 33 lks
- I-4 East $\frac{1}{2}$ Corner of Section 10. OBT'S: Beech 8, N46^oW, 17 lks
- 2 East 1/16 Corner on the Northside of Section 10. Not previously set

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-3 Corner set M.P.O.L. between N.W. Section Corner and N.E. Corner of Section 10
- I-4 Corner set M.P.O.L. between N.E. Section Corner and S.E. Corner of Section 10
- 2 Corner set M.P.O.L. between N.E. Section Corner and N $\frac{1}{2}$ Corner of Section 10

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|---|---------------------------------------|
| H-3 8" Maple, S38 ^o E, 24.0' | I-4 6" Balsam S14 ^o W, 16.9' | 2 6" Aspen, N18 ^o W, 4.65' |
| 10" Maple, S43 ^o W, 10.1' | 4" W. Birch S88 ^o W, 17.2' | 8" Balsam, N64 ^o E, 7.1' |
| 6" Ironwood, West, 15.65' | 8" Maple North, 32.2' | 10" Spruce, S38 ^o E, 10.1' |
| 14" W. Birch, N14 ^o W, 19.15' | 3" Maple N25 ^o E, 18.0' | 12" W. Pine, West, 18.7' |
| | Centerline of Road East 21.2' | |

SIGNED BY Gerald L. Wiggins DATE 5-18-87

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

