

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

CHIPPEWA CO.

3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION	6 T. 41 N. 6 E. 6 X R. X	B-2, 12, B1-5
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-2 Center of Section 6. Not previously set.
- 12 South 1/16 Corner of Section 6. Not previously set.
- B1-5 1/64 Corner on East side of N.E. 1/4, N.W. 1/4. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-2 Corner lies West of trail. Corner set at intersection of N.-S. 1/4 line and E.-W. 1/4 of Section 6.
- 12 Corner buried on south side of trail to camp. Location Post lies 5' East. Corner set M.P.O.L. between Center Corner and South 1/4 Corner of Section 6.
- B1-5 Corner set M.P.O.L. between corner code B-1 and computed 5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-2 DNR Monument. 10" Cedar, N60°E, 17.95' & 8" Cedar, N20° E, 30.7' & 10" Cedar, N13°W, 25.6' & 10" Cedar, S11°W, 32.9'
- 12 1" pipe w/Plastic Cap. 20" Cedar, S13°E, 35.8' & 12" Maple, S44°E, 29.75' & 8" Beech, S83°E, 24.4' & 14" Beech, N75°E, 22.5'.
- B1-5 DNR Monument. 24" Hemlock, S55°E, 25.0' & 16" Hemlock, N86°E, 35.0' & 8" W. Birch, N65° W. 20.0', & 8" Cedar, S6°E, 34.4'.

SIGNED BY Gerald L. Wiggins DATE 6-30-88

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET