

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
CHIPPEWA CO. 4 CORNERS.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. _____ N. _____ E. _____ S., R. _____ W. | _____ |
| 2. PROPERTY CONTROLLING IN SECTION _____ | 6 T. 41 N. _____ E. _____ R. 6 W. | 4, 1-4, 1, 3 |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ E. _____ S., R. _____ W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 4 N.W. 1/16 Corner of Section 6. Not previously set.
- I-4 1/64 Corner on West side N.E. 1/4, N.W. 1/4. Not previously set.
- 1 West 1/16 Corner on North side of Section 6. Not previously set.
- 3 North 1/16 Corner on West side of Section 6. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 4 Corner set at center of N.W. 1/4 of Section 6 by closed traverse.
- I-4 Corner set M.P.O.L. between corner code 1 and 4.
- 1 Corner set M.P.O.L. between N.W. Corner and North 1/4 Corner of Section 6.
- 3 Corner set M.P.O.L. between N.W. Corner and West 1/4 Corner of Section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- DNR Monument set at all four corners.
- 4 8" Cedar, S8°E, 1.95' & 8" Cedar, N77°E, 10.0' & 12" Cedar, N10°E, 26.8' & 10" Cedar, S76°W, 16.9".
- I-4 Sq. Post, S35°W, 0.5' & 8" Cedar, S40°W, 9.5' & 14" D. Cedar, N15°E, 20.0' & 12" D. Cedar, N50°E, 34.5'.
- 1 8" Cedar, N61°E, 10.2' & 8" Cedar, N35°E, 9.2' & 8" Cedar, S84°W, 8.15' & 6" Cedar, S40°E, 10.4'.
- 3 12" Cedar, S9°W, 7.15' & 7" Cedar, S70°E, 10.0' & 10" Cedar, N70°E, 3.20' & 14" Cedar, N2°W, 25.5'.

SIGNED BY Gerald L. Wiggins DATE 6-30-88


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET