

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

CHIPPEWA CO.

3 CORNERS

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 6 E.	A-6, A-7-10, C-6
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

Filed 8-10-89

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-30, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- A-6 West 1/4 Corner of Section 18. OBT'S: None.
 - A-7-10 Meander Corner between Sections 13 and 18 on South side of Knutsen Lake. OBT'S: Set Post & Cedar 6", N52°W, 43 lks.
 - C-6 East 1/4 Corner of Section 18. OBT'S: Fir 8", N22°W, 27 lks. & Fir 6", S71°W, 27 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-6 Corner set on line and single proportionate distance from original meander corner North side Knutsen Lake and original S.W. corner of Section 18.
- A-7-10 Corner set on line and single proportionate measure from original meander corner North side Knutsen Lake and original S.W. corner of Section 18.
- C-6 Corner set midpoint on line between N.E. Corner and S.E. Corner of Section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6 Corner in Lake, no monument set. A-7-10 DNR Monument. C-6 DNR Monument.
- Placed witness monument 688.0'
East on E-W 1/4 Line of Sec. 18.
- | | | |
|---------------------------|-------------------------|-------------------------|
| 10" Cedar, N15°E, 24.0' | 10" Cedar, S45°E, 13.2' | 12" Cedar, S72°W, 8.3' |
| 14" W. Pine, N85°E, 30.5' | 8" Cedar, S34°W, 17.4' | 10" Cedar, N30°W, 14.7' |
| 8" Cedar, S35°E, 6.3' | 8" Cedar, S60°W, 20.5' | 10" Cedar, N80°E, 33.5' |
| 10" W. Pine, S48°W, 6.6' | 8" Cedar, S76°W, 16.9' | 10" Cedar, S39°E, 59.6' |

SIGNED BY Gerald L. Wiggins DATE 6-13-89


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET