

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
CHIPPEWA CO. 3 CORNERS

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. R. <u>6</u> E.	M.C. 16
2. PROPERTY CONTROLLING IN SECTION <u>18</u>	T. <u>41</u> N. R. <u>6</u> E.	8, 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

8-10-89  
GFW

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-18-87 & 5-30, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 16 Meander Corner between Sections 7 and 18 on East side of Pats Lake. DBT'S: Set Post & Cedar 8", N21°E, 57 lks.
  - 8 West 1/16 Corner of Section 18. Not previously set.
  - 2 East 1/16 Corner of Section 18. Not previously set.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 16 Corner set on line between original Meander Corner West side Pats Lake and S.E. Corner of Section 7, 523.39' West of computed East 1/16 Corner between Sections 7 and 18.
  - 8 Corner set midpoint on line between computed West 1/4 Corner in lake and computed center of section in lake.
  - 2 Corner set midpoint on line between East 1/4 Corner and computed Center Corner of Section 18.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |                        |                         |                          |
|------------------------|-------------------------|--------------------------|
| 16 DNR Marked M.C.     | 8 DNR Monument          | 2 DNR Monument           |
| 8" Cedar, N50°W, 16.8' | 10" Cedar, N40°E, 7.7'  | 8" Cedar, N24°W, 12.4'   |
| 6" Cedar, N12°W, 6.1'  | 8" Cedar, S60°E, 10.4'  | 10" Cedar, N07°E, 17.3'  |
| 6" Cedar, N61°E, 10.1' | 10" Cedar, S45°W, 20.3' | 12" Cedar, N56°E, 19.65' |
| 5" Cedar, N80°E, 22.2' | 8" Cedar, S54°W, 15.0'  | 5" Cedar, S73°E, 9.25'   |

SIGNED BY Gerald L. Wiggins DATE 6-14-89  
Gerald L. Wiggins


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET